

# **State Water Resources Control Board**



#### **Division of Water Quality**

1001 I Street • Sacramento, California 95814 • (916) 341-5537 Mailing Address: P.O. Box 1977 • Sacramento, California • 95812-1977 FAX (916) 341-5543 • Internet Address: http://www.swrcb.ca.gov

To:	CONSTRUCTION STORM WATER DISCHARGER
SUBJECT:	CHECKLIST FOR SUBMITTING A NOTICE OF INTENT
In order for the State Water Resources Control Board to expeditiously process your Notice of Intent (NOI), the following items must be submitted to either of the addresses indicated below:	
1	NOI (please keep a copy for your files) with all applicable sections completed and original signature of the landowner or signatory agent;
2	Check made out to the "State Water Resources Control Board" for \$700.00; and
3	Site Map of the facility (see NOI instructions). DO NOT SEND BLUEPRINTS

#### **U.S. Postal Service Address**

State Water Resources Control Board Division of Water Quality Attn: Storm Water Section P.O. Box 1977 Sacramento, CA 95812-1977

# **Overnight Mailing Address**

State Water Resources Control Board Division Of Water Quality Attn: Storm Water, 15<sup>th</sup> Floor 1001 I Street Sacramento, CA 95814

NOIs are processed in the order they are received. A NOI receipt letter will be mailed to the land owner within approximately two weeks. Incomplete NOI submittals will be returned to the landowner's address within the same timeframe and will specify the reason(s) for return. If you need a receipt letter by a specific date (for example, to provide to a local agency), we advise that you submit your NOI thirty (30) days prior to the date the receipt letter is needed.

Please do not call us to verify your NOI status. A copy of your NOI receipt letter will be available on our web page within twenty-four (24) hours of processing. Go to: <a href="http://esmr.swrcb.ca.gov:7778/dwq/ConReceiptLetter.asp">http://esmr.swrcb.ca.gov:7778/dwq/ConReceiptLetter.asp</a> to retrieve an electronic copy of your NOI receipt letter. If you have any questions regarding this matter, please contact us at (916) 341-5537.

# FACT SHEET FOR WATER QUALITY ORDER 99-08-DWQ

# STATE WATER RESOURCES CONTROL BOARD (SWRCB) 901 P STREET, SACRAMENTO, CALIFORNIA 95814

# NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) GENERAL PERMIT FOR STORM WATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY (GENERAL PERMIT)

#### BACKGROUND

In 1972, the Federal Water Pollution Control Act (also referred to as the Clean Water Act [CWA]) was amended to provide that the discharge of pollutants to waters of the United States from any point source is unlawful unless the discharge is in compliance with an NPDES permit. The 1987 amendments to the CWA added Section 402(p) which establishes a framework for regulating municipal and industrial storm water discharges under the NPDES Program. On November 16, 1990, the U.S. Environmental Protection Agency (USEPA) published final regulations that establish storm water permit application requirements for specified categories of industries. The regulations provide that discharges of storm water to waters of the United States from construction projects that encompass five (5) or more acres of soil disturbance are effectively prohibited unless the discharge is in compliance with an NPDES Permit. Regulations (Phase II Rule) that became final on December 8, 1999 expand the existing NPDES program to address storm water discharges from construction sites that disturb land equal to or greater than one (1) acre and less than five (5) acres (small construction activity). The regulations require that small construction activity, other than those regulated under an individual or Regional Water Quality Control Board General Permit, must be permitted no later than March 10, 2003.

While federal regulations allow two permitting options for storm water discharges (individual permits and General Permits), the SWRCB has elected to adopt only one statewide General Permit at this time that will apply to all storm water discharges associated with construction activity, except from those on Tribal Lands, in the Lake Tahoe Hydrologic Unit, and those performed by the California Department of Transportation (Caltrans). Construction on Tribal Lands is regulated by an USEPA permit, the Lahontan Regional Water Control Board adopted a separate NPDES permit for the Lake Tahoe Hydrologic Unit, and the SWRCB adopted a separate NPDES permit for Caltrans projects. This General Permit requires all dischargers where construction activity disturbs one acre or more, to:

1. Develop and implement a Storm Water Pollution Prevention Plan (SWPPP) which specifies Best Management Practices (BMPs) that will prevent all construction pollutants from contacting storm water and with the intent of keeping all products of erosion from moving off site into receiving waters.

- 2. Eliminate or reduce nonstorm water discharges to storm sewer systems and other waters of the nation.
- 3. Perform inspections of all BMPs.

This General Permit shall be implemented and enforced by the nine California Regional Water Quality Control Boards (RWQCBs).

The General Permit accompanying this fact sheet regulates storm water runoff from construction sites. Regulating many storm water discharges under one permit will greatly reduce the otherwise overwhelming administrative burden associated with permitting individual storm water discharges. Dischargers shall submit a Notice of Intent (NOI) to obtain coverage under this General Permit. It is expected that as the storm water program develops, the RWQCBs may issue General Permits or individual permits containing more specific permit provisions. When this occurs, those dischargers will no longer be regulated by this General Permit.

On August 19, 1999, the State Water Resources Control Board (SWRCB) reissued the General Construction Storm Water Permit (Water Quality Order 99-08-DWQ referred to as "General Permit"). The San Francisco BayKeeper, Santa Monica BayKeeper, San Diego BayKeeper, and Orange Coast Keeper filed a petition for writ of mandate challenging the General Permit in the Superior Court, County of Sacramento. The Court issued a judgment and writ of mandate on September 15, 2000. The Court directed the SWRCB to modify the provisions of the General Permit to require permittees to implement specific sampling and analytical procedures to determine whether Best Management Practices (BMPs) implemented on a construction site are: (1) preventing further impairment by sediment in storm waters discharged directly into waters listed as impaired for sediment or silt, and (2) preventing other pollutants, that are known or should be known by permittees to occur on construction sites and that are not visually detectable in storm water discharges, from causing or contributing to exceedances of water quality objectives. The monitoring provisions in the General Permit have been modified pursuant to the court order.

#### TYPES OF CONSTRUCTION ACTIVITY COVERED BY THIS GENERAL PERMIT

Construction activity subject to this General Permit includes clearing, grading, disturbances to the ground such as stockpiling, or excavation that results in soil disturbances of at least one acre of total land area. Construction activity that results in soil disturbances of less than one acre is subject to this General Permit if the construction activity is part of a larger common plan of development that encompasses one or more acres of soil disturbance or if there is significant water quality impairment resulting from the activity. Construction activity does not include routine maintenance to maintain original line and grade, hydraulic capacity, or original purpose of the facility, nor does it include emergency construction activities required to protect public health and safety. Dischargers should confirm with the local RWQCB whether or not a particular routine maintenance activity is subject to this General Permit.

A construction project which includes a dredge and/or fill discharge to any jurisdictional surface water (e.g., wetland, channel, pond, or marine water) will also need a CWA Section 404 permit from the U.S. Army Corps of Engineers and a CWA Section 401 Water Quality Certification from the RWQCB/SWRCB. Storm water discharges from dredge spoil placement which occurs outside of Corps jurisdiction (upland sites) and are part of construction activity which disturbs one or more acres of land are covered by this general permit. Proponents of construction projects which disturb one or more acres of land within the jurisdictional boundaries of a CWA Section 404 permit should contact the local RWQCB to determine the applicability of this permit to the project.

#### NOTIFICATION REQUIREMENTS

It is the responsibility of the landowner to obtain coverage under this General Permit prior to commencement of construction activities. To obtain coverage, the landowner must file an NOI with a vicinity map and the appropriate fee with the SWRCB. In addition, coverage under this permit shall not occur until the applicant develops an adequate SWPPP for the project. Section A of the General Permit outlines the required contents of a SWPPP. For proposed construction activity on easements or on nearby property by agreement or permission, the entity responsible for the construction activity shall file an NOI and filing fee and shall be responsible for development of the SWPPP, all of which must occur prior to commencement of construction activities.

A separate NOI shall be submitted to the SWRCB for each construction site. Owners of new construction shall file an NOI prior to the commencement of construction. Owners of an ongoing construction site that is covered under the previous General Construction Permit (WQ Order No.92-08-DWQ) (1) shall continue to implement their existing SWPPP and monitoring program and (2) shall implement any necessary revisions to their SWPPP in a timely manner but in no case later than 90-calender days from adoption of this General Permit in accordance with Section A of this General Permit.

The NOI requirements of the General Permit are intended to establish a mechanism which can be used to clearly identify the responsible parties, locations, and scope of operations of dischargers covered by the General Permit and to document the discharger's knowledge of the requirements for a SWPPP.

The NOI must be sent to the following address:

State Water Resources Control Board Division of Water Quality Storm Water Permit Unit P.O. Box 1977 Sacramento, CA 95812-1977

The current annual fee for this General Permit is \$700.

When construction is complete or ownership has been transferred, dischargers shall file a Notice of Termination with the RWQCB certifying that all State and local requirements have been met in accordance with Special Provisions for Construction Activity, C.7, of the General Permit.

Dischargers who fail to obtain coverage under this General Permit for storm water discharges to surface waters will be in violation of the CWA and the California Water Code.

#### CONSTRUCTION ACTIVITY NOT COVERED BY THIS GENERAL PERMIT

This General Permit does not apply to storm water discharges from (1) those areas on Tribal Lands; (2) the Lake Tahoe Hydrologic Unit; (3) construction under one acre, unless part of a larger common plan of development or sale; (4) projects covered by an individual NPDES Permit for storm water discharges associated with construction activity; and (5) landfill construction that is subject to the general industrial permit.

Storm water discharges in the Lake Tahoe Hydrologic Unit are regulated by a separate permit(s) adopted by the California Regional Water Quality Control Board, Lahontan Region (LRWQCB). USEPA regulates storm water discharges on Tribal Lands. Permit applications for storm water discharges that will be conducted in the Lake Tahoe Hydrologic Unit must be submitted directly to the LRWQCB.

#### **DESCRIPTION OF GENERAL PERMIT CONDITIONS**

The following is a brief description of the major provisions of the General Permit and the basis for the General Permit.

#### **Prohibitions**

This General Permit authorizes the discharge of storm water to surface waters from construction activities that result in the disturbance of one or more acres of land. It prohibits the discharge of materials other than storm water and authorized non-storm water discharges and all discharges which contain a hazardous substance in excess of reportable quantities established at 40 Code of Federal Regulations (CFR) 117.3 or 40 CFR 302.4 unless a separate NPDES Permit has been issued to regulate those discharges. In addition, this General Permit contains provisions that uphold discharge prohibitions contained in water quality control plans, as implemented through the nine RWQCBs.

#### **Effluent Limitations**

Permits for storm water discharges associated with construction activity shall meet all applicable provisions of Sections 301 and 402 of the CWA. These provisions require controls of pollutant discharges that utilize best available technology economically achievable (BAT) and best conventional pollutant control technology (BCT) to reduce pollutants and any more stringent controls necessary to meet water quality standards.

It is not feasible at this time for the SWRCB to establish numeric effluent limitations. The reasons why it is not feasible to establish numeric effluent limitations are discussed in detail in SWRCB Order Nos. WQ 91-03 and WQ 91-04. Therefore, the effluent limitations contained in this General Permit are narrative and include the requirement to implement appropriate BMPs. The BMPs shall primarily emphasize source controls such as erosion control and pollution prevention methods. The discharger shall also install structural controls, as necessary, such as sediment control which will constitute BAT and BCT and will achieve compliance with water quality standards. The narrative effluent limitations constitute compliance with the requirements of the CWA.

Elimination or reduction of nonstorm water discharges is a major goal of this General Permit. Nonstorm water discharges include a wide variety of sources, including improper dumping, spills, or leakage from storage tanks or transfer areas. Nonstorm water discharges may contribute a significant pollutant load to receiving waters. Measures to control spills, leakage, and dumping and to prevent illicit connections during construction shall be addressed through structural as well as non-structural BMPs.

This General Permit prohibits the discharge of materials other than storm water and authorized nonstorm water discharges. It is recognized that certain nonstorm water discharges may be necessary for the completion of construction projects. Such discharges include, but are not limited to irrigation of vegetative erosion control measures, pipe flushing and testing, street cleaning, and dewatering. Such discharges are allowed by this General Permit provided they are not relied upon to clean up failed or inadequate construction or post-construction BMPs designed to keep materials onsite. These authorized nonstorm water discharges shall (1) be infeasible to eliminate, (2) comply with BMPs as described in the SWPPP, and (3) not cause or contribute to a violation of water quality standards. Additionally, these discharges may be required to be permitted by the local RWQCB (e.g., some RWQCBs have adopted General Permits for dewatering discharges). This General Permit is performance-based to the extent that it prohibits the discharge of storm water that causes or threatens to cause pollution, contamination, or nuisance; but it also allows the owner/developer to determine the most economical, effective, and possibly innovative BMPs.

The requirements of this General Permit are intended to be implemented on a year-round basis, not just during the part of the year when there is a high probability of a precipitation event which results in storm water runoff. The permit should be implemented at the appropriate level and in a proactive manner during all seasons while construction is ongoing.

Weather and storm predictions or weather information concerning the 10-year, 6-hour storm event and mean annual rainfall can be obtained by calling the Western Regional Climate Center at 775-674-7010 or via the internet at www.wrcc.dri.edu/precip.html and/or www.wrcc.dri.edu/pcpnfreq.html.

#### Receiving Water Limitations Language

The receiving water limitations language is fundamentally different from the language adopted in the SWRCB General Industrial Activities Storm Water Permit on April 17, 1997. Construction related activities which cause or contribute to an exceedance of water quality standards must be corrected immediately and cannot wait for the RWQCB to approve a plan of action to correct. The dynamic nature of construction activity allows the discharger the ability to more quickly identify and correct the source of the exceedances. Therefore, the owner is required to take immediate corrective action and to provide a report to the appropriate RWQCB within

14-calendar days of the violation describing the corrective action.

#### Storm Water Pollution Prevention Plan (SWPPP)

This General Permit requires development and implementation of a SWPPP. This document emphasizes the use of appropriately selected, correctly installed and maintained pollution reduction BMPs. This approach provides the flexibility necessary to establish BMPs which can effectively address source control of pollutants during changing construction activities.

All dischargers shall prepare and implement a SWPPP prior to disturbing a site. The SWPPP must be implemented at the appropriate level to protect water quality at all times throughout the life of the project. Nonstorm water BMPs must be implemented year round. The SWPPP shall remain on the site while the site is under construction, commencing with the initial mobilization and ending with the termination of coverage under the permit.

The SWPPP has two major objectives: (1) to help identify the sources of sediment and other pollutants that affect the quality of storm water discharges and (2) to describe and ensure the implementation of BMPs to reduce or eliminate sediment and other pollutants in storm water as well as nonstorm water discharges. The SWPPP shall include BMPs which address source control and, if necessary, shall also include BMPs which address pollutant control.

Required elements of a SWPPP include: (1) site description addressing the elements and characteristics specific to the site, (2) descriptions of BMPs for erosion and sediment controls, (3) BMPs for construction waste handling and disposal, (4) implementation of approved local plans, (5) proposed post-construction controls, including description of local post-construction erosion and sediment control requirements, and (6) nonstorm water management.

To ensure that the preparation, implementation, and oversight of the SWPPP is sufficient for effective pollution prevention, individuals responsible for creating, revising, overseeing, and implementing the SWPPP should participate in applicable training programs and document such training in the SWPPP.

SWPPPs are reports that are available to the public under Section 308(b) of the CWA and will be made available by the RWQCB upon request.

Monitoring Program

Another major feature of the General Permit is the development and implementation of a monitoring program. All dischargers are required to conduct inspections of the construction site

prior to anticipated storm events and after actual storm events. During extended storm events, inspections must be made during each 24-hour period. The goals of these inspections are (1) to identify areas contributing to a storm water discharge; (2) to evaluate whether measures to reduce pollutant loadings identified in the SWPPP are adequate and properly installed and functioning in accordance with the terms of the General Permit; and (3) whether additional control practices or corrective maintenance activities are needed. Equipment, materials, and workers must be available for rapid response to failures and emergencies. All corrective maintenance to BMPs shall be performed as soon as possible, depending upon worker safety.

Each discharger shall certify annually that the construction activities are in compliance with the requirements of this General Permit. Dischargers who cannot certify annual compliance shall notify the appropriate RWQCB. A well-developed monitoring program will provide a good method for checking the effectiveness of the SWPPP.

## Retention of Records

The discharger is required to retain records of all monitoring information, copies of all reports required by this General Permit, and records of all data used to complete the NOI for all construction activities to be covered by the General Permit for a period of at least three years from the date generated. This period may be extended by request of the SWRCB and/or RWQCB. With the exception of reporting noncompliance to the appropriate RWQCB, dischargers are not required to submit the records, except upon specific request by the RWQCB.

# STATE WATER RESOURCES CONTROL BOARD (SWRCB) ORDER NO. 99 - 08 - DWQ NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) GENERAL PERMIT NO. CAS000002

# WASTE DISCHARGE REQUIREMENTS (WDRS) FOR DISCHARGES OF STORM WATER RUNOFF ASSOCIATED WITH CONSTRUCTION ACTIVITY

#### The State Water Resources Control Board finds that:

1. Federal regulations for controlling pollutants in storm water runoff discharges were promulgated by the U.S. Environmental Protection Agency (USEPA) on November 16, 1990 (40 Code of Federal Regulations (CFR) Parts 122, 123, and 124). The regulations require discharges of storm water to surface waters associated with construction activity including clearing, grading, and excavation activities (except operations that result in disturbance of less than five acres of total land area and which are not part of a larger common plan of development or sale) to obtain an NPDES permit and to implement Best Available Technology Economically Achievable (BAT) and Best Conventional Pollutant Control Technology (BCT) to reduce or eliminate storm water pollution.

On December 8, 1999 federal regulations promulgated by USEPA (40CFR Parts 9, 122, 123, and 124) expanded the NPDES storm water program to include storm water discharges from municipal separate storm sewer systems (MS4s) and construction sites that were smaller than those previously included in the program. Federal regulation 40 CFR § 122.26(b)(15) defines small construction activity as including clearing, grading, and excavating that result in land disturbance of equal to or greater than one acre or less than five acres or is part of a larger common plan of development or sale. Permit applications for small construction activities are due by March 10, 2003.

- 2. This General Permit regulates pollutants in discharges of storm water associated with construction activity (storm water discharges) to surface waters, except from those areas on Tribal Lands; Lake Tahoe Hydrologic Unit; construction projects which disturb less than one acre, unless part of a larger common plan of development or sale; and storm water discharges which are determined ineligible for coverage under this General Permit by the California Regional Water Quality Control Boards (RWQCBs). Attachment 1 contains addresses and telephone numbers of each RWQCB office.
- 3. This General Permit does not preempt or supersede the authority of local storm water management agencies to prohibit, restrict, or control storm water discharges to separate storm sewer systems or other watercourses within their jurisdiction, as allowed by State and Federal law.

- 4. To obtain authorization for proposed storm water discharges to surface waters, pursuant to this General Permit, the landowner (discharger) must submit a Notice of Intent (NOI) with a vicinity map and the appropriate fee to the SWRCB prior to commencement of construction activities. In addition, coverage under this General Permit shall not occur until the applicant develops a Storm Water Pollution Prevention Plan (SWPPP) in accordance with the requirements of Section A of this permit for the project. For proposed construction activity conducted on easements or on nearby property by agreement or permission, or by an owner or lessee of a mineral estate (oil, gas, geothermal, aggregate, precious metals, and/or industrial minerals) entitled to conduct the activities, the entity responsible for the construction activity must submit the NOI and filing fee and shall be responsible for development of the SWPPP.
- 5. If an individual NPDES Permit is issued to a discharger otherwise subject to this General Permit or if an alternative General Permit is subsequently adopted which covers storm water discharges regulated by this General Permit, the applicability of this General Permit to such discharges is automatically terminated on the effective date of the individual permit or the date of approval for coverage under the subsequent General Permit.
- 6. This action to adopt an NPDES permit is exempt from the provisions of the California Environmental Quality Act (Public Resources Code Section 21100, et seq.) in accordance with section 13389 of the California Water Code.
- 7. The SWRCB adopted the California Ocean Plan, and the RWQCBs have adopted and the SWRCB has approved Water Quality Control Plans (Basin Plans). Dischargers regulated by this General Permit must comply with the water quality standards in these Basin Plans and subsequent amendments thereto.
- 8. The SWRCB finds storm water discharges associated with construction activity to be a potential significant sources of pollutants. Furthermore, the SWRCB finds that storm water discharges associated with construction activities have the reasonable potential to cause or contribute to an excursion above water quality standards for sediment in the water bodies listed in Attachment 3 to this permit.
- 9. It is not feasible at this time to establish numeric effluent limitations for pollutants in storm water discharges from construction activities. Instead, the provisions of this General Permit require implementation of Best Management Practices (BMPs) to control and abate the discharge of pollutants in storm water discharges.
- 10. Discharges of non-storm water may be necessary for the completion of certain construction projects. Such discharges include, but are not limited to: irrigation of vegetative erosion control measures, pipe flushing and testing, street cleaning, and dewatering. Such discharges are authorized by this General Permit as long as they (a) do comply with Section A.9 of this General Permit, (b) do not cause or contribute to violation of any water quality standard, (c) do not violate any other provision of this

General Permit, (d) do not require a non-storm water permit as issued by some RWQCBs, and (e) are not prohibited by a Basin Plan. If a non-storm water discharge is subject to a separate permit adopted by a RWQCB, the discharge must additionally be authorized by the RWQCB permit.

- 11. Following adoption of this General Permit, the RWQCBs shall enforce the provisions herein including the monitoring and reporting requirements.
- 12. Following public notice in accordance with State and Federal laws and regulations, the SWRCB in a public meeting on June 8, 1998, heard and considered all comments. The SWRCB has prepared written responses to all significant comments.
- 13. This Order is an NPDES permit in compliance with section 402 of the Clean Water Act (CWA) and shall take effect upon adoption by the SWRCB provided the Regional Administrator of the USEPA has no objection. If the USEPA Regional Administrator objects to its issuance, the General Permit shall not become effective until such objection is withdrawn.
- 14. This General Permit does not authorize discharges of fill or dredged material regulated by the U.S. Army Corps of Engineers under CWA section 404 and does not constitute a waiver of water quality certification under CWA section 401.
- The Monitoring Program and Reporting Requirements are modified in compliance with a judgment in the case of <u>San Francisco BayKeeper</u>, et al. v. <u>State Water Resources</u>

  <u>Control Board</u>. The modifications include sampling and analysis requirements for direct discharges of sediment to waters impaired due to sediment and for pollutants that are not visually detectable in runoff that may cause or contribute to an exceedance of water quality objectives.
- Storm water discharges associated with industrial activity that are owned or operated by municipalities serving populations less than 100,000 people are no longer exempt from the need to apply for or obtain a storm water discharge permit. A temporary exemption, which was later extended by USEPA, was provided under section 1068(c) of the Intermodal Surface Transportation and Efficiency Act (ISTEA) of 1991. Federal regulation 40 CFR § 122.26(e)(1)(ii) requires the above municipalities to submit permit application by March 10, 2003.
- 17 This permit may be reopened and modified to include different monitoring requirements for small construction activity than for construction activity over five (5) acres.

IT IS HEREBY ORDERED that all dischargers who file an NOI indicating their intention to be regulated under the provisions of this General Permit shall comply with the following:

#### A. DISCHARGE PROHIBITIONS:

- 1. Authorization pursuant to this General Permit does not constitute an exemption to applicable discharge prohibitions prescribed in Basin Plans, as implemented by the nine RWQCBs.
- 2. Discharges of material other than storm water which are not otherwise authorized by an NPDES permit to a separate storm sewer system (MS4) or waters of the nation are prohibited, except as allowed in Special Provisions for Construction Activity, C.3.
- 3. Storm water discharges shall not cause or threaten to cause pollution, contamination, or nuisance.
- 4. Storm water discharges regulated by this General Permit shall not contain a hazardous substance equal to or in excess of a reportable quantity listed in 40 CFR Part 117 and/or 40 CFR Part 302.

#### B. RECEIVING WATER LIMITATIONS:

- 1. Storm water discharges and authorized nonstorm water discharges to any surface or ground water shall not adversely impact human health or the environment.
- 2. The SWPPP developed for the construction activity covered by this General Permit shall be designed and implemented such that storm water discharges and authorized nonstorm water discharges shall not cause or contribute to an exceedance of any applicable water quality standards contained in a Statewide Water Quality Control Plan and/or the applicable RWQCB's Basin Plan.
- 3. Should it be determined by the discharger, SWRCB, or RWQCB that storm water discharges and/or authorized nonstorm water discharges are causing or contributing to an exceedance of an applicable water quality standard, the discharger shall:
  - a. Implement corrective measures immediately following discovery that water quality standards were exceeded, followed by notification to the RWQCB by telephone as soon as possible but no later than 48 hours after the discharge has been discovered. This notification shall be followed by a report within 14-calender days to the appropriate RWQCB, unless otherwise directed by the RWQCB, describing (1) the nature and cause of the water quality standard exceedance; (2) the BMPs currently being implemented; (3) any additional BMPs which will be implemented to

prevent or reduce pollutants that are causing or contributing to the exceedance of water quality standards; and (4) any maintenance or repair of BMPs. This report shall include an implementation schedule for corrective actions and shall describe the actions taken to reduce the pollutants causing or contributing to the exceedance.

- b. The discharger shall revise its SWPPP and monitoring program immediately after the report to the RWQCB to incorporate the additional BMPs that have been and will be implemented, the implementation schedule, and any additional monitoring needed.
- c. Nothing in this section shall prevent the appropriate RWQCB from enforcing any provisions of this General Permit while the discharger prepares and implements the above report.

#### C. SPECIAL PROVISIONS FOR CONSTRUCTION ACTIVITY:

- 1. All dischargers shall file an NOI and pay the appropriate fee for construction activities conducted at each site as required by Attachment 2: Notice of Intent-General Instructions.
- 2. All dischargers shall develop and implement a SWPPP in accordance with Section A: Storm Water Pollution Prevention Plan. The discharger shall implement controls to reduce pollutants in storm water discharges from their construction sites to the BAT/BCT performance standard.
- 3. Discharges of non-storm water are authorized only where they do not cause or contribute to a violation of any water quality standard and are controlled through implementation of appropriate BMPs for elimination or reduction of pollutants. Implementation of appropriate BMPs is a condition for authorization of non-storm water discharges. Non-storm water discharges and the BMPs appropriate for their control must be described in the SWPPP. Wherever feasible, alternatives which do not result in discharge of nonstorm water shall be implemented in accordance with Section A.9. of the SWPPP requirements.
- 4. All dischargers shall develop and implement a monitoring program and reporting plan in accordance with Section B: Monitoring Program and Reporting Requirements.
- 5. All dischargers shall comply with the lawful requirements of municipalities, counties, drainage districts, and other local agencies regarding discharges of storm water to separate storm sewer systems or other watercourses under their jurisdiction, including applicable requirements in municipal storm water management programs developed to comply with NPDES permits issued by the RWQCBs to local agencies.

- 6. All dischargers shall comply with the standard provisions and reporting requirements contained in Section C: Standard Provisions.
- 7. The discharger may terminate coverage for a portion of the project under this General Permit when ownership of a portion of this project has been transferred or when a phase within this multi-phase project has been completed. When ownership has transferred, the discharger must submit to its RWQCB a Change of Information Form (COI) Attachment 4 with revised site map and the name, address and telephone number of the new owner(s). Upon transfer of title, the discharger should notify the new owner(s) of the need to obtain coverage under this General Permit. The new owner must comply with provisions of Sections A. 2. (c) and
  - B. 2. (b) of this General Permit. To terminate coverage for a portion of the project when a phase has been completed, the discharger must submit to its RWQCB a COI with a revised map that identifies the newly delineated site.
- 8. The discharger may terminate coverage under this General Permit for a complete project by submitting to its RWQCB a Notice of Termination Form (NOT), and the post-construction BMPs plan according to Section A.10 of this General Permit. Note that a construction project is considered complete only when all portions of the site have been transferred to a new owner; or the following conditions have been met:
  - a. There is no potential for construction related storm water pollution,
  - b. All elements of the SWPPP have been completed,
  - c. Construction materials and waste have been disposed of properly,
  - d. The site is in compliance with all local storm water management requirements, and
  - e. A post-construction storm water management plan is in place as described in the site's SWPPP.
- 9. This General Permit expires five years from the date of adoption.

#### D. REGIONAL WATER QUALITY CONTROL BOARD (RWQCB) AUTHORITIES:

#### 1. RWQCBs shall:

- a. Implement the provisions of this General Permit. Implementation of this General Permit may include, but is not limited to requesting the submittal of SWPPPS, reviewing SWPPPs, reviewing monitoring reports, conducting compliance inspections, and taking enforcement actions.
- b. Issue permits as they deem appropriate to individual dischargers, categories of dischargers, or dischargers in a geographic area. Upon issuance of such permits by a RWQCB, the affected dischargers shall no longer be regulated by this General Permit.
- 2. RWQCBs may require, on a case-by-case basis, the inclusion of an analysis of potential downstream impacts on receiving waterways due to the permitted construction.
- 3. RWQCBs may provide information to dischargers on the development and implementation of SWPPPs and monitoring programs and may require revisions to SWPPPs and monitoring programs.
- 4. RWQCBs may require dischargers to retain records for more than three years.
- 5. RWQCBs may require additional monitoring and reporting program requirements including sampling and analysis of discharges to water bodies listed in Attachment 3 to this permit. Additional requirements imposed by the RWQCB should be consistent with the overall monitoring effort in the receiving waters.
- 6. RWQCBs may issue individual NPDES permits for those construction activities found to be ineligible for coverage under this permit.

#### **CERTIFICATION**

The undersigned, Administrative Assistant to the Board, does hereby certify that the foregoing is a full, true, and correct copy of an order duly and regularly adopted at a meeting of the State Water Resources Control Board held on August 19, 1999.

AYE: James M. Stubchaer

Mary Jane Forster John W. Brown

Arthur G. Baggett, Jr.

NO: None

ABSENT: None

ABSTAIN: None

/s/

Maureen Marché Administrative Assistant to the Board

#### SECTION A: STORM WATER POLLUTION PREVENTION PLAN

#### 1. Objectives

A Storm Water Pollution Prevention Plan (SWPPP) shall be developed and implemented to address the specific circumstances for each construction site covered by this General Permit. The SWPPP shall be certified in accordance with the signatory requirements of section C, Standard Provision for Construction Activities (9). The SWPPP shall be developed and amended or revised, when necessary, to meet the following objectives:

- a. Identify all pollutant sources including sources of sediment that may affect the quality of storm water discharges associated with construction activity (storm water discharges) from the construction site, and
- b. Identify non-storm water discharges, and
- c. Identify, construct, implement in accordance with a time schedule, and maintain Best Management Practices (BMPs) to reduce or eliminate pollutants in storm water discharges and authorized nonstorm water discharges from the construction site during construction, and
- d. Develop a maintenance schedule for BMPs installed during construction designed to reduce or eliminate pollutants after construction is completed (post-construction BMPs).
- e. Identify a sampling and analysis strategy and sampling schedule for discharges from construction activity which discharge directly into water bodies listed on Attachment 3. (Clean Water Act Section 303(d) [303(d)] Water Bodies listed for Sedimentation).
- f. For all construction activity, identify a sampling and analysis strategy and sampling schedule for discharges that have been discovered through visual monitoring to be potentially contaminated by pollutants not visually detectable in the runoff.

#### 2. <u>Implementation Schedule</u>

- a. For construction activity commencing on or after adoption of this General Permit, the SWPPP shall be developed prior to the start of soil-disturbing activity in accordance with this Section and shall be implemented concurrently with commencement of soil-disturbing activities.
- b. Existing permittees engaging in construction activities covered under the terms of the previous General Construction Permit SWPPP (WQ Order No.92-08-DWQ) shall continue to implement their existing SWPPP and shall implement any

necessary revisions to their SWPPP in accordance with this Section of the General Permit in a timely manner, but in no case more than 90-calender days from the date of adoption of this General Permit.

- c. For ongoing construction activity involving a change of ownership of property, the new owner shall review the existing SWPPP and amend if necessary, or develop a new SWPPP within 45-calender days.
- d. Existing permittees shall revise their SWPPP in accordance with the sampling and analysis modifications prior to August 1, 2001. For ongoing construction activity involving a change of ownership the new owner shall review the existing SWPPP and amend the sampling and analysis strategy, if required, within 45 days. For construction activity commencing after the date of adoption, the SWPPP shall be developed in accordance with the modification language adopted.

## 3. Availability

The SWPPP shall remain on the construction site while the site is under construction during working hours, commencing with the initial construction activity and ending with termination of coverage under the General Permit.

# 4. Required Changes

- a. The discharger shall amend the SWPPP whenever there is a change in construction or operations which may affect the discharge of pollutants to surface waters, ground waters, or a municipal separate storm sewer system (MS4). The SWPPP shall also be amended if the discharger violates any condition of this General Permit or has not achieved the general objective of reducing or eliminating pollutants in storm water discharges. If the RWQCB determines that the discharger is in violation of this General Permit, the SWPPP shall be amended and implemented in a timely manner, but in no case more than 14-calendar days after notification by the RWQCB. All amendments should be dated and directly attached to the SWPPP.
- b. The RWQCB or local agency with the concurrence of the RWQCB may require the discharger to amend the SWPPP.

#### 5. Source Identification

The SWPPP shall include: (a) project information and (b) pollutant source identification combined with an itemization of those BMPs specifically chosen to control the pollutants listed.

#### a. Project Information

- (1) The SWPPP shall include a vicinity map locating the project site with respect to easily identifiable major roadways, geographic features, or landmarks. At a minimum, the map must show the construction site perimeter, the geographic features surrounding the site, and the general topography.
- (2) The SWPPP shall include a site map(s) which shows the construction project in detail, including the existing and planned paved areas and buildings.
  - (a) At a minimum, the map must show the construction site perimeter; existing and proposed buildings, lots, roadways, storm water collection and discharge points; general topography both before and after construction; and the anticipated discharge location(s) where the storm water from the construction site discharges to a municipal storm sewer system or other water body.
  - (b) The drainage patterns across the project area must clearly be shown on the map, and the map must extend as far outside the site perimeter as necessary to illustrate the relevant drainage areas. Where relevant drainage areas are too large to depict on the map, map notes or inserts illustrating the upstream drainage areas are sufficient.
  - (c) Temporary on-site drainages to carry concentrated flow shall be selected to comply with local ordinances, to control erosion, to return flows to their natural drainage courses, and to prevent damage to downstream properties.
- 3. Information presented in the SWPPP may be represented either by narrative or by graphics. Where possible, narrative descriptions should be plan notes. Narrative descriptions which do not lend themselves to plan notes can be contained in a separate document which must be referenced on the plan.

#### b. Pollutant Source and BMP Identification

The SWPPP shall include a description of potential sources which are likely to add pollutants to storm water discharges or which may result in nonstorm water discharges from the construction site. Discharges originating from off-site which flow across or through areas disturbed by construction that may contain pollutants should be reported to the RWQCB.

The SWPPP shall:

- (1) Show drainage patterns and slopes anticipated after major grading activities are completed. Runoff from off-site areas should be prevented from flowing through areas that have been disturbed by construction unless appropriate conveyance systems are in place. The amount of anticipated storm water run-on must be considered to determine the appropriateness of the BMPs chosen. Show all calculations for anticipated storm water run-on, and describe all BMPs implemented to divert off-site drainage described in section A. 5 a. (2) (c) around or through the construction project.
- (2) Show the drainage patterns into each on-site storm water inlet point or receiving water. Show or describe the BMPs that will protect operational storm water inlets or receiving waters from contaminated discharges other than sediment discharges, such as, but not limited to: storm water with elevated pH levels from contact with soil amendments such as lime or gypsum; slurry from sawcutting of concrete or asphalt; washing of exposed aggregate concrete; concrete rinse water; building washing operations; equipment washing operations; minor street washing associated with street delineation; and/or sealing and paving activities occurring during rains.
- (3) Show existing site features that, as a result of known past usage, may contribute pollutants to storm water, (e.g., toxic materials that are known to have been treated, stored, disposed, spilled, or leaked onto the construction site). Show or describe the BMPs implemented to minimize the exposure of storm water to contaminated soil or toxic materials.
- (4) Show areas designated for the (a) storage of soil or waste, (b) vehicle storage and service areas, (c) construction material loading, unloading, and access areas, (d) equipment storage, cleaning, and maintenance areas.
- (5) Describe the BMPs for control of discharges from waste handling and disposal areas and methods of on-site storage and disposal of construction materials and construction waste. Describe the BMPs designed to minimize or eliminate the exposure of storm water to construction materials, equipment, vehicles, waste storage areas, or service areas. The BMPs described shall be in compliance with Federal, State, and local laws, regulations, and ordinances.
- (6) Describe all post-construction BMPs for the project, and show the location of each BMP on the map. (Post-construction BMPs consist of permanent features designed to minimize pollutant discharges, including sediment, from the site after construction has been completed.) Also, describe the agency or parties to be the responsible party for long-term maintenance of these BMPs.

- (7) Show the locations of direct discharge from the construction site into a Section 303(d) list water body. Show the designated sampling locations in the receiving waters, which represent the prevailing conditions of the water bodies upstream of the construction site discharge and immediately downstream from the last point of discharge.
- (8) Show the locations designated for sampling the discharge from areas identified in Section A. 5. b. (2), (3), and (4) and Section A. 5. c. (1) and (2). Samples shall be taken should visual monitoring indicate that there has been a breach, malfunction, leakage, or spill from a BMP which could result in the discharge in storm water of pollutants that would not be visually detectable, or if storm water comes into contact with soil amendments or other exposed materials or contamination and is allowed to be discharged. Describe the sampling procedure, location, and rationale for obtaining the uncontaminated sample of storm water.

#### c. Additional Information

- (1) The SWPPP shall include a narrative description of pollutant sources and BMPs that cannot be adequately communicated or identified on the site map. In addition, a narrative description of preconstruction control practices (if any) to reduce sediment and other pollutants in storm water discharges shall be included.
- (2) The SWPPP shall include an inventory of all materials used and activities performed during construction that have the potential to contribute to the discharge of pollutants other than sediment in storm water. Describe the BMPs selected and the basis for their selection to eliminate or reduce these pollutants in the storm water discharges.
- (3) The SWPPP shall include the following information regarding the construction site surface area: the size (in acres or square feet), the runoff coefficient before and after construction, and the percentage that is impervious (e.g., paved, roofed, etc.) before and after construction.
- (4) The SWPPP shall include a copy of the NOI, and the Waste Discharge Identification (WDID) number. Should a WDID number not be received from the SWRCB at the time construction commences, the discharger shall include proof of mailing of the NOI, e.g., certified mail receipt, copy of check, express mail receipt, etc.
- (5) The SWPPP shall include a construction activity schedule which describes all major activities such as mass grading, paving, lot or parcel

improvements at the site and the proposed time frame to conduct those activities.

(6) The SWPPP shall list the name and telephone number of the qualified person(s) who have been assigned responsibility for prestorm, poststorm, and storm event BMP inspections; and the {PRIVATE }qualified person(s) assigned responsibility to ensure full compliance with the permit and implementation of all elements of the SWPPP, including the preparation of the annual compliance evaluation and the elimination of all unauthorized discharges.

#### 6. <u>Erosion Control</u>

Erosion control, also referred to as "soil stabilization" is the most effective way to retain soil and sediment on the construction site. The most efficient way to address erosion control is to preserve existing vegetation where feasible, to limit disturbance, and to stabilize and revegetate disturbed areas as soon as possible after grading or construction. Particular attention must be paid to large mass-graded sites where the potential for soil exposure to the erosive effects of rainfall and wind is great. Mass graded construction sites may be exposed for several years while the project is being built out. Thus, there is potential for significant sediment discharge from the site to surface waters.

At a minimum, the discharger/operator must implement an effective combination of erosion and sediment control on all disturbed areas during the rainy season. These disturbed areas include rough graded roadways, slopes, and building pads. Until permanent vegetation is established, soil cover is the most cost-effective and expeditious method to protect soil particles from detachment and transport by rainfall. Temporary soil stabilization can be the single-most important factor in reducing erosion at construction sites. The discharger shall consider measures such as: covering with mulch, temporary seeding, soil stabilizers, binders, fiber rolls or blankets, temporary vegetation, permanent seeding, and a variety of other measures.

The SWPPP shall include a description of the erosion control practices, including a time schedule, to be implemented during construction to minimize erosion on disturbed areas of a construction site. The discharger must consider the full range of erosion control BMPs. The discharger must consider any additional site-specific and seasonal conditions when selecting and implementing appropriate BMPs. The above listed erosion control measures are examples of what should be considered and are not exclusive of new or innovative approaches currently available or being developed.

#### a. The SWPPP shall include:

- (1) An outline of the areas of vegetative soil cover or native vegetation onsite which will remain undisturbed during the construction project.
- (2) An outline of all areas of soil disturbance including cut or fill areas which will be stabilized during the rainy season by temporary or permanent erosion control measures, such as seeding, mulch, or blankets, etc.
- (3) An outline of the areas of soil disturbance, cut, or fill which will be left exposed during any part of the rainy season, representing areas of potential soil erosion where sediment control BMPs are required to be used during construction.
- (4) A proposed schedule for the implementation of erosion control measures.
- b. The SWPPP shall include a description of the BMPs and control practices to be used for both temporary and permanent erosion control measures.
- c. The SWPPP shall include a description of the BMPs to reduce wind erosion at all times, with particular attention paid to stock-piled materials.

#### 7. Stabilization

- (1) All disturbed areas of the construction site must be stabilized. Final stabilization for the purposes of submitting a NOT is satisfied when:
  - -All soil disturbing activities are completed AND EITHER OF THE TWO FOLLOWING CRITERIA ARE MET:
  - -A uniform vegetative cover with 70 percent coverage has been established OR:
  - -equivalent stabilization measures have been employed. These measures include the use of such BMPs as blankets, reinforced channel liners, soil cement, fiber matrices, geotextiles, or other erosion resistant soil coverings or treatments.
- Where background native vegetation covers less than 100 percent of the surface, such as in arid areas, the 70 percent coverage criteria is adjusted as follows: If the native vegetation covers 50 percent of the ground surface, 70 percent of 50 percent (.70 X .50=.35) would require 35 percent total uniform surface coverage.

#### 8. <u>Sediment Control</u>

The SWPPP shall include a description or illustration of BMPs which will be implemented to prevent a net increase of sediment load in storm water discharge relative to preconstruction levels. Sediment control BMPs are required at appropriate locations along the site perimeter and at all operational internal inlets to the storm drain system at all times during the rainy season. Sediment control practices may include filtration devices and barriers (such as fiber rolls, silt fence, straw bale barriers, and gravel inlet filters) and/or settling devices (such as sediment traps or basins). Effective filtration devices, barriers, and settling devices shall be selected, installed and maintained properly. A proposed schedule for deployment of sediment control BMPs shall be included in the SWPPP. These are the most basic measures to prevent sediment from leaving the project site and moving into receiving waters. Limited exemptions may be authorized by the RWQCB when work on active areas precludes the use of sediment control BMPs temporarily. Under these conditions, the SWPPP must describe a plan to establish perimeter controls prior to the onset of rain.

During the nonrainy season, the discharger is responsible for ensuring that adequate sediment control materials are available to control sediment discharges at the downgrade perimeter and operational inlets in the event of a predicted storm. The discharger shall consider a full range of sediment controls, in addition to the controls listed above, such as straw bale dikes, earth dikes, brush barriers, drainage swales, check dams, subsurface drain, sandbag dikes, fiber rolls, or other controls. At a minimum, the discharger/operator must implement an effective combination of erosion and sediment control on all disturbed areas during the rainy season.

If the discharger chooses to rely on sediment basins for treatment purposes, sediment basins shall, at a minimum, be designed and maintained as follows:

Option 1: Pursuant to local ordinance for sediment basin design and maintenance, provided that the design efficiency is as protective or more protective of water quality than Option 3.

OR

Option 2: Sediment basin(s), as measured from the bottom of the basin to the principal outlet, shall have at least a capacity equivalent to 3,600 cubic feet of storage per acre draining into the sediment basin. The length of the basin shall be more than twice the width of the basin. The length is determined by measuring the distance between the inlet and the outlet; and the depth must not be less than three feet nor greater than five feet for safety reasons and for maximum efficiency.

OR

Option 3: Sediment basin(s) shall be designed using the standard equation:

As=1.2Q/Vs

Where: As is the minimum surface area for trapping soil particles of a certain size; Vs is the settling velocity of the design particle size chosen; and Q=C x I x A where Q is the discharge rate measured in cubic feet per second; C is the runoff coefficient; I is the precipitation intensity for the 10-year, 6-hour rain event and A is the area draining into the sediment basin in acres. The design particle size shall be the smallest soil grain size determined by wet sieve analysis, or the fine silt sized (0.01mm) particle, and the Vs used shall be 100 percent of the calculated settling velocity.

The length is determined by measuring the distance between the inlet and the outlet; the length shall be more than twice the dimension as the width; the depth shall not be less than three feet nor greater than five feet for safety reasons and for maximum efficiency (two feet of storage, two feet of capacity). The basin(s) shall be located on the site where it can be maintained on a year-round basis and shall be maintained on a schedule to retain the two feet of capacity;

OR

Option 4: The use of an equivalent surface area design or equation, provided that the design efficiency is as protective or more protective of water quality than Option 3.

A sediment basin shall have a means for dewatering within 7-calendar days following a storm event. Sediment basins may be fenced if safety (worker or public) is a concern.

The outflow from a sediment basin that discharges into a natural drainage shall be provided with outlet protection to prevent erosion and scour of the embankment and channel

The discharger must consider any additional site-specific and seasonal conditions when selecting and designing sediment control BMPs. The above listed sediment control measures are examples of what should be considered and are not exclusive of new or innovative approaches currently available or being developed.

The SWPPP shall include a description of the BMPs to reduce the tracking of sediment onto public or private roads at all times. These public and private roads shall be inspected and cleaned as necessary. Road cleaning BMPs shall be discussed in the SWPPP and will not rely on the washing of accumulated sediment or silt into the storm drain system.

#### 9. Non-Storm Water Management

Describe all non-storm water discharges to receiving waters that are proposed for the construction project. Non-storm water discharges should be eliminated or reduced to the extent feasible. Include the locations of such discharges and descriptions of all BMPs designed for the control of pollutants in such discharges. Onetime discharges shall be monitored during the time that such discharges are occurring. A qualified person should be assigned the responsibility for ensuring that no materials other than storm water are discharged in quantities which will have an adverse effect on receiving waters or storm drain systems (consistent with BAT/BCT), and the name and contact number of that person should be included in the SWPPP document.

Discharging sediment-laden water which will cause or contribute to an exceedance of the applicable RWQCB's Basin Plan from a dewatering site or sediment basin into any receiving water or storm drain without filtration or equivalent treatment is prohibited.

# 10. Post-Construction Storm Water Management

The SWPPP shall include descriptions of the BMPs to reduce pollutants in storm water discharges after all construction phases have been completed at the site (Post-Construction BMPs). Post-Construction BMPs include the minimization of land disturbance, the minimization of impervious surfaces, treatment of storm water runoff using infiltration, detention/retention, biofilter BMPs, use of efficient irrigation systems, ensuring that interior drains are not connected to a storm sewer system, and appropriately designed and constructed energy dissipation devices. These must be consistent with all local post-construction storm water management requirements, policies, and guidelines. The discharger must consider site-specific and seasonal conditions when designing the control practices. Operation and maintenance of control practices after construction is completed shall be addressed, including short-and long-term funding sources and the responsible party.

#### 11. Maintenance, Inspection, and Repair

The SWPPP shall include a discussion of the program to inspect and maintain all BMPs as identified in the site plan or other narrative documents throughout the entire duration of the project. A qualified person will be assigned the responsibility to conduct inspections. The name and telephone number of that person shall be listed in the SWPPP document. Inspections will be performed before and after storm events and once each 24-hour period during extended storm events to identify BMP effectiveness and implement repairs or design changes as soon as feasible depending upon field conditions. Equipment, materials, and workers must be available for rapid response to failures and emergencies. All corrective maintenance to BMPs shall be performed as soon as possible after the conclusion of each storm depending upon worker safety.

For each inspection required above, the discharger shall complete an inspection checklist. At a minimum, an inspection checklist shall include:

#### a. Inspection date.

- b. Weather information: best estimate of beginning of storm event, duration of event, time elapsed since last storm, and approximate amount of rainfall (inches).
- c. A description of any inadequate BMPs.
- d. If it is possible to safely access during inclement weather, list observations of all BMPs: erosion controls, sediment controls, chemical and waste controls, and non-storm water controls. Otherwise, list result of visual inspection at relevant outfall, discharge point, or downstream location and projected required maintenance activities.
- e. Corrective actions required, including any changes to SWPPP necessary and implementation dates.
- f. Inspectors name, title, and signature.

The dischargers shall prepare their inspection checklists using the inspection checklist form provided by the SWRCB or RWQCB or on forms that contain the equivalent information.

#### 12. <u>Training</u>

Individuals responsible for SWPPP preparation, implementation, and permit compliance shall be appropriately trained, and the SWPPP shall document all training. This includes those personnel responsible for installation, inspection, maintenance, and repair of BMPs. Those responsible for overseeing, revising, and amending the SWPPP shall also document their training. Training should be both formal and informal, occur on an ongoing basis when it is appropriate and convenient, and should include training/workshops offered by the SWRCB, RWQCB, or other locally recognized agencies or professional organizations.

#### 13. List of Contractors/Subcontractors

The SWPPP shall include a list of names of all contractors, (or subcontractors) and individuals responsible for implementation of the SWPPP. This list should include telephone numbers and addresses. Specific areas of responsibility of each subcontractor and emergency contact numbers should also be included.

#### 14. Other Plans

This SWPPP may incorporate by reference the appropriate elements of other plans required by local, State, or Federal agencies. A copy of any requirements incorporated by reference shall be kept at the construction site.

## 15. Public Access

The SWPPP shall be provided, upon request, to the RWQCB. The SWPPP is considered a report that shall be available to the public by the RWQCB under section 308(b) of the Clean Water Act.

#### 16. Preparer Certification

The SWPPP and each amendment shall be signed by the landowner (discharger) or his representative and include the date of initial preparation and the date of each amendment.

#### SECTION B: MONITORING PROGRAM AND REPORTING REQUIREMENTS

# 1. Required Changes

The RWQCB may require the discharger to conduct additional site inspections, to submit reports and certifications, or perform sampling and analysis.

#### 2. <u>Implementation</u>

- a. The requirements of this Section shall be implemented at the time of commencement of construction activity (see also Section A. 2. Implementation Schedule). The discharger is responsible for implementing these requirements until construction activity is complete and the site is stabilized.
- b. For ongoing construction activity involving a change in ownership of property covered by this General Permit, the new owner must complete a NOI and implement the requirements of this Section concurrent with the change of ownership. For changes of information, the owner must follow instructions in C. 7. Special Provisions for Construction Activity of the General Permit.

#### 3. Site Inspections

Qualified personnel shall conduct inspections of the construction site prior to anticipated storm events, during extended storm events, and after actual storm events to identify areas contributing to a discharge of storm water associated with construction activity. The name(s) and contact number(s) of the assigned inspection personnel shall be listed in the SWPPP. Pre-storm inspections are to ensure that BMPs are properly installed and maintained; post-storm inspections are to assure that the BMPs have functioned adequately. During extended storm events, inspections shall be required each 24-hour period. Best Management Practices (BMPs) shall be evaluated for adequacy and proper implementation and whether additional BMPs are required in accordance with the terms of the General Permit (see language in Section A. 11. Maintenance, Inspection, and Repair). Implementation of nonstorm water discharge BMPs shall be verified and their

effectiveness evaluated. One time discharges of non-storm water shall be inspected when such discharges occur.

# 4. <u>Compliance Certification</u>

Each discharger or qualified assigned personnel listed by name and contact number in the SWPPP must certify annually that construction activities are in compliance with the requirements of this General Permit and the SWPPP. This Certification shall be based upon the site inspections required in Item 3 of this Section. The certification must be completed by July 1 of each year.

# 5. <u>Noncompliance Reporting</u>

Dischargers who cannot certify compliance, in accordance with Item 4 of this Section and/or who have had other instances of noncompliance excluding exceedances of water quality standards as defined in section B. 3. Receiving Water Limitations Language, shall notify the appropriate RWQCB within 30 days. Corrective measures should be implemented immediately following discovery that water quality standards were exceeded. The notifications shall identify the noncompliance event, including an initial assessment of any impact caused by the event; describe the actions necessary to achieve compliance; and include a time schedule subject to the modifications by the RWQCB indicating when compliance will be achieved. Noncompliance notifications must be submitted within 30-calendar days of identification of noncompliance.

#### 6. Monitoring Records

Records of all inspections, compliance certifications, and noncompliance reporting must be retained for a period of at least three years from the date generated. With the exception of noncompliance reporting, dischargers are not required to submit these records.

## 7. Monitoring Program for Sedimentation/Siltation

Dischargers of storm water associated with construction activity that directly enters a water body listed in Attachment 3 shall conduct a sampling and analysis program for the pollutants (sedimentation/siltation or turbidity) causing the impairment. The discharger shall monitor for the applicable parameter. If the water body is listed for sedimentation or siltation, samples should be analyzed for Settleable Solids (ml/l) and Total Suspended Solids (mg/l). Alternatively or in addition, samples may be analyzed for suspended sediment concentration according to ASTM D3977-97. If the water body is listed for turbidity, samples should be analyzed for turbidity (NTU). Discharges that flow through tributaries that are not listed in Attachment 3 or that flow into Municipal Separate Storm Sewer Systems (MS4) are not subject to these sampling and analysis requirements. The sampling and analysis parameters and procedures must be designed to determine whether the BMPs installed and maintained prevent discharges of sediment from contributing to impairment in receiving waters.

Samples shall be collected during the first two hours of discharge from rain events which result in a direct discharge to any water body listed in Attachment 3. Samples shall be collected during daylight hours (sunrise to sunset). Dischargers need not collect more than four (4) samples per month. All samples shall be taken in the receiving waters and shall be representative of the prevailing conditions of the water bodies. Samples shall be collected from safely accessible locations upstream of the construction site discharge and immediately downstream from the last point of discharge.

For laboratory analysis, all sampling, sample preservation, and analyses must be conducted according to test procedures under 40 CFR Part 136. Field samples shall be collected and analyzed according to the specifications of the manufacturer of the sampling devices employed. Portable meters shall be calibrated according to manufacturer's specification. All field and/or laboratory analytical data shall be kept in the SWPPP document, which is to remain at the construction site at all times until a Notice of Termination has been submitted and approved.

#### 8. Monitoring Program for Pollutants Not Visually Detectable in Storm Water

A sampling and analysis program shall be developed and conducted for pollutants which are not visually detectable in storm water discharges, which are or should be known to occur on the construction site, and which could cause or contribute to an exceedance of water quality objectives in the receiving water. Pollutants that should be considered for inclusion in this sampling and analysis program are those identified in Sections A.5.b. and A.5.c.

Construction materials and compounds that are not stored in water-tight containers under a water-tight roof or inside a building are examples of materials for which the discharger may have to implement sampling and analysis procedures. The goal of the sampling and analysis is to determine whether the BMPs employed and maintained on site are effective in preventing the potential pollutants from coming in contact with storm water and causing or contributing to an exceedance of water quality objectives in the receiving waters. Examples of construction sites that may require sampling and analysis include: sites that are known to have contaminants spilled or spread on the ground; sites where construction practices include the application of soil amendments, such as gypsum, which can increase the pH of the runoff; or sites having uncovered stockpiles of material exposed to storm water. Visual observations before, during, and after storm events may trigger the requirement to collect samples. Any breach, malfunction, leakage, or spill observed which could result in the discharge of pollutants to surface waters that would not be visually detectable in storm water shall trigger the collection of a sample of discharge. Samples shall be collected at all discharge locations which drain the areas identified by the visual observations and which can be safely accessed. For sites where sampling and analysis is required, personnel trained in water quality sampling procedures shall collect storm water samples. A sufficiently large sample of storm water that has not come in contact with the disturbed soil or the materials stored or used on-site

(uncontaminated sample) shall be collected for comparison with the discharge sample. Samples shall be collected during the first two hours of discharge from rain events that occur during daylight hours and which generate runoff.

The uncontaminated sample shall be compared to the samples of discharge using field analysis or through laboratory analysis. Analyses may include, but are not limited to, indicator parameters such as: pH, specific conductance, dissolved oxygen, conductivity, salinity, and TDS.

For laboratory analysis, all sampling, sample preservation, and analyses must be conducted according to test procedures under 40 CFR Part 136. Field discharge samples shall be collected and analyzed according to the specifications of the manufacturer of the sampling devices employed. Portable meters shall be calibrated according to manufacturer's specification. All field and/or analytical data shall be kept in the SWPPP document, which is to remain at the construction site at all times until a *Notice of* Termination has been submitted and approved.

#### SECTION C: STANDARD PROVISIONS FOR CONSTRUCTION ACTIVITY

# 1. <u>Duty to Comply</u>

The discharger must comply with all of the conditions of this General Permit. Any permit noncompliance constitutes a violation of the Clean Water Act (CWA) and the Porter-Cologne Water Quality Control Act and is grounds for enforcement action and/or removal from General Permit coverage.

The discharger shall comply with effluent standards or prohibitions established under Section 307(a) of the CWA for toxic pollutants within the time provided in the regulations that establish these standards or prohibitions, even if this General Permit has not yet been modified to incorporate the requirement.

#### 2. General Permit Actions

This General Permit may be modified, revoked and reissued, or terminated for cause. The filing of a request by the discharger for a General Permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance does not annul any General Permit condition.

If any toxic effluent standard or prohibition (including any schedule of compliance specified in such effluent standard or prohibition) is promulgated under Section 307(a) of the CWA for a toxic pollutant which is present in the discharge and that standard or prohibition is more stringent than any limitation on the pollutant in this General Permit, this General Permit shall be modified or revoked and reissued to conform to the toxic effluent standard or prohibition and the dischargers so notified.

# 3. Need to Halt or Reduce Activity Not a Defense

It shall not be a defense for a discharger in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this General Permit.

## 4. <u>Duty to Mitigate</u>

The discharger shall take all responsible steps to minimize or prevent any discharge in violation of this General Permit, which has a reasonable likelihood of adversely affecting human health or the environment.

# 5. Proper Operation and Maintenance

The discharger shall at all times properly operate and maintain any facilities and systems of treatment and control (and related appurtenances) which are installed or used by the discharger to achieve compliance with the conditions of this General Permit and with the requirements of Storm Water Pollution Prevention Plans (SWPPP). Proper operation and maintenance also includes adequate laboratory controls and appropriate quality assurance procedures. Proper operation and maintenance may require the operation of backup or auxiliary facilities or similar systems installed by a discharger when necessary to achieve compliance with the conditions of this General Permit.

# 6. <u>Property Rights</u>

This General Permit does not convey any property rights of any sort or any exclusive privileges, nor does it authorize any injury to private property or any invasion of personal rights, nor does it authorize any infringement of Federal, State, or local laws or regulations.

#### 7. Duty to Provide Information

The discharger shall furnish the RWQCB, State Water Resources Control Board, or USEPA, within a reasonable time, any requested information to determine compliance with this General Permit. The discharger shall also furnish, upon request, copies of records required to be kept by this General Permit.

# 8. <u>Inspection and Entry</u>

The discharger shall allow the RWQCB, SWRCB, USEPA, and/or, in the case of construction sites which discharge through a municipal separate storm sewer, an authorized representative of the municipal operator of the separate storm sewer system receiving the discharge, upon the presentation of credentials and other documents as may be required by law, to:

- a. Enter upon the discharger's premises at reasonable times where a regulated construction activity is being conducted or where records must be kept under the conditions of this General Permit;
- b. Access and copy at reasonable times any records that must be kept under the conditions of this General Permit;
- c. Inspect at reasonable times the complete construction site, including any off-site staging areas or material storage areas, and the erosion/sediment controls; and
- d. Sample or monitor at reasonable times for the purpose of ensuring General Permit compliance.

# 9. <u>Signatory Requirements</u>

- a. All Notice of Intents (NOIs), Notice of Terminations (NOTs), SWPPPs, certifications, and reports prepared in accordance with this Order submitted to the SWRCB shall be signed as follows:
  - (1) For a corporation: by a responsible corporate officer. For the purpose of this Section, a responsible corporate officer means: (a) a president, secretary, treasurer, or vice president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision-making functions for the corporation, or (b) the manager of the construction activity if authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures;
  - (2) For a partnership or sole proprietorship: by a general partner or the proprietor, respectively; or
  - (3) For a municipality, State, Federal, or other public agency: by either a principal executive officer, ranking elected official, or duly authorized representative. The principal executive officer of a Federal agency includes the chief executive officer of the agency or the senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g., Regional Administrator of USEPA).
  - b. All SWPPPs, reports, certifications, or other information required by the General Permit and/or requested by the RWQCB, SWRCB, USEPA, or the local storm water management agency shall be signed by a person described above or by a duly authorized representative. A person is a duly authorized representative if:
    - (1) The authorization is made in writing by a person described above and retained as part of the SWPPP; or

- (2) The authorization specifies either an individual or a position having responsibility for the overall operation of the construction activity, such as the position of manager, operator, superintendent, or position of equivalent responsibility, or an individual or position having overall responsibility for environmental matters for the company. (A duly authorized representative may thus be either a named individual or any individual occupying a named position).
- c. If an authorization is no longer accurate because a different individual or position has responsibility for the overall operation of the construction activity, a new authorization must be attached to the SWPPP prior to submittal of any reports, information, or certifications to be signed by the authorized representative.

## 10. <u>Certification</u>

Any person signing documents under Section C, Provision 9 above, shall make the following certification:

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, to the best of my knowledge and belief, the information submitted is, true, accurate, and complete.

I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

# 11. Anticipated Noncompliance

The discharger will give advance notice to the RWQCB and local storm water management agency of any planned changes in the construction activity which may result in noncompliance with General Permit requirements.

# 12. <u>Penalties for Falsification of Reports</u>

Section 309(c)(4) of the CWA provides that any person who knowingly makes any false material statement, representation, or certification in any record or other document submitted or required to be maintained under this General Permit, including reports of compliance or noncompliance shall upon conviction, be punished by a fine of not more than \$10,000 or by imprisonment for not more than two years or by both.

## 13. Oil and Hazardous Substance Liability

Nothing in this General Permit shall be construed to preclude the institution of any legal action or relieve the discharger from any responsibilities, liabilities, or penalties to which the discharger is or may be subject to under Section 311 of the CWA.

# 14. <u>Severability</u>

The provisions of this General Permit are severable; and, if any provision of this General Permit or the application of any provision of this General Permit to any circumstance is held invalid, the application of such provision to other circumstances and the remainder of this General Permit shall not be affected thereby.

# 15. Reopener Clause

This General Permit may be modified, revoked and reissued, or terminated for cause due to promulgation of amended regulations, receipt of USEPA guidance concerning regulated activities, judicial decision, or in accordance with 40 Code of Federal Regulations (CFR) 122.62, 122.63, 122.64, and 124.5.

#### 16. Penalties for Violations of Permit Conditions

- a. Section 309 of the CWA provides significant penalties for any person who violates a permit condition implementing Sections 301, 302, 306, 307, 308, 318, or 405 of the CWA or any permit condition or limitation implementing any such section in a permit issued under Section 402. Any person who violates any permit condition of this General Permit is subject to a civil penalty not to exceed \$27,500 per calendar day of such violation, as well as any other appropriate sanction provided by Section 309 of the CWA.
- b. The Porter-Cologne Water Quality Control Act also provides for civil and criminal penalties which in some cases are greater than those under the CWA.

# 17. Availability

A copy of this General Permit shall be maintained at the construction site during construction activity and be available to operating personnel.

# 18. <u>Transfers</u>

This General Permit is not transferable. A new owner of an ongoing construction activity must submit a NOI in accordance with the requirements of this General Permit to be authorized to discharge under this General Permit. An owner who sells property covered

by this General Permit shall inform the new owner of the duty to file a NOI and shall provide the new owner with a copy of this General Permit.

# 19. <u>Continuation of Expired Permit</u>

This General Permit continues in force and effect until a new General Permit is issued or the SWRCB rescinds this General Permit. Only those dischargers authorized to discharge under the expiring General Permit are covered by the continued General Permit.

# SWRCB AND RWQCB CONTACT LIST

Please see Storm Water Contacts at http://www.swrcb.ca.gov/stormwtr/contact.html

# NOTICE OF INTENT (NOI) TO COMPLY WITH THE TERMS OF THE GENERAL PERMIT TO DISCHARGE STORM WATER ASSOCIATED WITH CONSTRUCTION ACTIVITY

#### **GENERAL INSTRUCTIONS**

#### Who Must Submit

Discharges of storm water associated with construction that results in the disturbance of one acre or more of land must apply for coverage under the General Construction Activities Storm Water Permit (General Permit). Construction activity which is a part of a larger common area of development or sale must also be permitted. (For example, if 4 acres of a 20-acre subdivision is disturbed by construction activities, and the remaining 16 acres is to be developed at a future date, the property owner must obtain a General Storm Water Permit for the 4-acre project). Construction activity includes, but is not limited to: clearing, grading, demolition, excavation, construction of new structures, and reconstruction of existing facilities involving removal and replacement that results in soil disturbance. This includes construction access roads, staging areas, storage areas, stockpiles, and any off-site areas which receive run-off from the construction project such as discharge points into a receiving water. Construction activity does not include routine maintenance to maintain original line and grade, hydraulic capacity, or original purpose of the facility.

The owner of the land where the construction activity is occurring is responsible for obtaining a permit. Owners may obtain coverage under the General Permit by filing a NOI in accordance with the following instructions. Coverage for construction activity conducted on easements (e.g., pipeline construction) or on nearby properties by agreement or permission, or by an owner or lessee of a mineral estate (oil, gas, geothermal, aggregate, precious metals, and/or industrial minerals) entitled to conduct the activities, shall be obtained by the entity responsible for the construction activity. Linear construction projects which will have construction activity occurring in one or more than one Region should contact the State Water Resources Control Board at the number listed below prior to submitting an NOI application for specific information related to the use of the NOI form.

#### Construction Activity Not Covered By This General Permit

Storm water discharges in the Lake Tahoe Hydrologic Unit will be regulated by a separate permit(s) adopted by the California Regional Water Quality Control Board, Lahontan Region, and will not be covered under the State Water Resources Control Board's (SWRCB) General Permit. Storm water discharges on Indian Lands will be regulated by the U.S. Environmental Protection Agency.

#### Where to Apply

The NOI form, vicinity map, and appropriate fee must be mailed to the SWRCB at the following address:

State Water Resources Control Board Division of Water Quality Attn: Storm Water Permit Unit P.O. Box 1977 Sacramento, CA 95812-1977

### When to Apply

Property owners proposing to conduct construction activities subject to this General Permit must file a Notice of Intent prior to the commencement of construction activity.

#### Fees

The annual fee is \$700 for all construction sites submitting an NOI. Checks should be made payable to: SWRCB.

#### Completing the Notice of Intent (NOI)

The submittal to obtain coverage under the General Permit must include a completed NOI Form (Notice of Intent, attached), a vicinity map, and the appropriate annual fee. The NOI must be completely and accurately filled out; the vicinity map and annual fee must be included with the NOI or the submittal is considered incomplete and will be rejected. A construction site is considered to be covered by the General Permit upon filing a complete NOI submittal, and implementation of a defensible Storm Water Pollution Prevention Plan (SWPPP). Upon receipt of a complete NOI submittal, each discharger will be sent a receipt letter containing the waste discharger's identification (WDID) number.

#### Questions?

If you have any questions on completing the NOI please call the SWRCB at (916) 341-5537.

#### **NOI-LINE-BY-LINE INSTRUCTIONS**

Please type or print when completing the NOI Form and vicinity map.

#### **SECTION I--NOI STATUS**

Mark one of the two boxes at the top portion of the NOI. Check box 1 if the NOI is being completed for new construction. Check box 2 if the NOI is being submitted to report changes for a construction site already covered by the General Permit. An example of a change that warrants a resubmittal of the NOI is a change of total area of the construction site. The permit is non-transferable, a change of ownership requires a Notice of Termination (NOT) submittal and a new NOI. Complete only those portions of the NOI that apply to the changes (the NOI must always be signed). If box 2 is checked, the WDID number must be included.

#### SECTION II--PROPERTY OWNER

Enter the construction site owner's official or legal name and address; contact person (if other than owner), title, and telephone number.

#### SECTION III--DEVELOPER / CONTRACTOR INFORMATION

Enter the name of the developer's (or general contractor's) official or legal name, address, contact person, title, and telephone number. The contact person should be someone who is familiar with the construction site and is responsible for compliance and oversight of the general permit.

#### SECTION IV-CONSTRUCTION PROJECT INFORMATION

Enter the project name, site address, county, city, (or nearest city if construction is occurring in an unincorporated area), zip code, and telephone number (if any) of the construction site. Include an emergency contact telephone or pager number. Construction site information should include latitude and longitude designations, tract numbers, and/or mile post markers, if applicable. The site contact person should be someone who is familiar with the project, site plans, SWPPP, and monitoring program. All NOIs must be accompanied by a vicinity map.

- Part A: Enter the total size in acres of all areas associated with construction activity, including all access roads.
- Part B: Enter the total size in acres of the area to be disturbed by construction activity and the percentage of the area listed in Part A above that this represents.
- Part C: Enter the percentage of the site that is impervious (areas where water cannot soak into the ground, such as concrete, asphalt, rooftops, etc.) before and after construction.
- Part D: Include tract numbers, if available.

- Part E: Enter the mile post marker number at the project site location.
- Part F: Indicate whether the construction site is part of a larger common plan of development or sale. For example, if the construction activity is occurring on a two-acre site which is within a development that is one acre or greater, answer yes.
- Part G: Enter the name of the development (e.g. "Quail Ridge Subdivision", "Orange Valley Estates", etc.).
- Part H: Indicate when construction will begin (month, day, year). When a NOI is being submitted due to a change in ownership, the commencement date should be the date the new ownership took effect.
- Part I: Indicate the percentage of the total project area to be mass graded.
- Part J: Enter the estimated completion dates for the mass grading activities and for the project completion.
- Part K: Indicate the type(s) of construction taking place. For example, "Transportation" should be checked for the construction of roads; "Utility" should be checked for installation of sewer, electric, or telephone systems. Include a description of the major construction activities, (e.g., 20 single family homes, a supermarket, an office building, a factory, etc.)

#### SECTION V--BILLING ADDRESS

To continue coverage under the General Permit, the annual fee must be paid. Indicate where the annual fee invoice should be mailed by checking one of the following boxes:

Owner: sent to the owners address as it appears in Section II.

Developer/Contractor: sent to the developer's address as it appears in Section III.

Other: sent to a different address and enter that address in the spaces provided.

#### SECTION VI--REGULATORY STATUS

Indicate whether or not the site is subject to local erosion/sediment control ordinances. Indicate whether the erosion/sediment control plan designed to comply with the ordinance addresses the construction of infrastructure and structures in addition to grading. Identify the name and telephone number of the local agency, if applicable.

#### SECTION VII--RECEIVING WATER INFORMATION

Part A: Indicate whether the storm water runoff from the construction site discharges indirectly to waters of the United States, directly to waters of the United States, or to a separate storm drain system.

Indirect discharges include discharges that may flow overland across adjacent properties or rights-of-way prior to discharging into waters of the United States.

Enter the name of the owner/operator of the relevant storm drain system, if applicable. Storm water discharges directly to waters of the United States will typically have an outfall structure directly from the facility to a river, lake, creek, stream, bay, ocean, etc. Discharges to separate storm sewer systems are those that discharge to a collection system operated by municipalities, flood control districts, utilities, or similar entities.

Part B: Enter the name of the receiving water. Regardless of point of discharge, the owner must determine the receiving water for the construction site's storm water discharge. Enter the name of the receiving water.

# SECTION VIII--IMPLEMENTATION OF NPDES PERMIT REQUIREMENTS

- Part A: Indicate the status of the SWPPP, date prepared, or availability for review. Also indicate if a tentative construction schedule has been included in the SWPPP (the inclusion of a construction activity schedule is a mandatory SWPPP requirement).
- Part B: Provide information concerning the status of the development of a monitoring program, a component of the SWPPP which outlines an inspection and maintenance schedule for the proposed Best Management Practices (BMPs). Provide name and phone number of program preparer.
- Part C: Provide the name and phone numbers of the responsible party or parties designated to insure compliance with all elements of the General Permit and SWPPP.

#### SECTION IX--VICINITY MAP AND FEE

Provide a "to scale" or "to approximate scale" drawing of the construction site and the immediate surrounding area. Whenever possible, limit the map to an 8.5" x 11' or 11" x 17" sheet of paper. At a minimum, the map must show the site perimeter, the geographic features surrounding the site, and general topography, and a north arrow. The map must also include the location of the construction project in relation to named streets, roads, intersections, or landmarks. A NOI containing a map which does not clearly indicate the location of the construction project will be rejected. Do not submit blueprints unless they meet the above referenced size limits.

#### SECTION X--CERTIFICATIONS

This section must be completed by the owner or signatory agent of the construction site\*. The certification provides assurances that the NOI and vicinity map were completed in an accurate and complete fashion and with the knowledge that penalties exist for providing false information. Certification also requires the owner to comply with the provisions in the General Permit.

<sup>\*</sup> For a corporation: a responsible corporate officer (or authorized individual). For a partnership or sole proprietorship: a general partner or the proprietor, respectively. For a municipality, State, Federal, or other public agency: either a principal executive officer, ranking elected official, or duly authorized representative.



State Water Resources Control Board

NOTICE OF INTENT
TO COMPLY WITH THE TERMS OF THE
GENERAL PERMIT TO DISCHARGE STORM WATER
ASSOCIATED WITH CONSTRUCTION ACTIVITY (WQ ORDER No. 99-08-DWQ)



I. NOI STATUS (SEE INSTRUCTIONS)								
MARK ONLY ONE ITEM 1. New Cor	nstruction 2.	nge of Ir	nformat	tion for WDID#				
II. PROPERTY OWNER								
Name		Contac	ct Persor	n				
Mailing Address		Title						
City		Stat e	Zip		Pi	hone		
					(	)	<del></del>	
III. DEVELOPER/CONTRACTOR INFOR	MATION	<del></del>						
Developer/Contractor	1	Contac	ct Persor	n				
Mailing Address	1	Title						
City		Stat e	Zip			Phone		
			<u> </u>			(	)	
IV. CONSTRUCTION PROJECT INFORM	MATION							
Site/Project Name		Site Co	ontact Pe	erson				
Physical Address/Location		Latitud	Latitude Longitude Co		County	unty		
	l		o	o				
City (or nearest City)		Zip		Site Phone Nu	ımber	Der Emergency Phone Number		
A. Total size of construction site area:	C. Percent of site imperviousness	includir (includir						
Acres	Before Construction:	D. Tract Number(s):,						
B. Total area to be disturbed:  Acres (% of total)	After Construction:	% E. Mile Post Marker:						
F. Is the construction site part of a larger common pl	an of development or sale?	G. Nar	me of pl	lan or developme	ent:			
☐ YES ☐ NO		<u> </u>	D : : ! = =4=	· · · · · · · · · · · · · · · · · · ·	*			
H. Construction commencement date:/	_/	J. Projected construction dates:						
I. % of site to be mass graded:	!	Comple	ete grad	ding:/	_/	Co	omplete project://_	
K. Type of Construction (Check all that apply):								
1. Residential 2. Commerci	ial 3. Industrial	4.	Re	construction	5.	] Tra	nsportation	
6. Utility Description:	<u></u>			List):			· 	
V. BILLING INFORMATION								
SEND BILL TO: Name					C	ontact Pe	'erson	
OWNER (as in II. above)								
DEVELOPER (as in III. above)  Mailing Address					PI	hone/Fax	х	
☐ OTHER					St	tate	Zip	
(enter information at								

VI. REGULATORY STATUS		
A. Has a local agency approved a required erosion/sediment control plan?		□ NO
Does the erosion/sediment control plan address construction activities such as infrastructure and structures?	YES	□ NO
Name of local agency: Phone: ( )		
B. Is this project or any part thereof, subject to conditions imposed under a CWA Section 404 permit of 401 Water Quality Certification?NO	YES	;
If yes, provide details:		
VII. RECEIVING WATER INFORMATION		
A. Does the storm water runoff from the construction site discharge to (Check all that apply):		_
1. Indirectly to waters of the U.S.		
2. Storm drain system - Enter owner's name:		
3. Directly to waters of U.S. (e.g. , river, lake, creek, stream, bay, ocean, etc.)		
B. Name of receiving water: (river, lake, creek, stream, bay, ocean):		
VIII. IMPLEMENTATION OF NPDES PERMIT REQUIREMENTS		
A. STORM WATER POLLUTION PREVENTION PLAN (SWPPP) (check one)		
A SWPPP has been prepared for this facility and is available for review: Date Prepared:// Date A	Amended:/	_/
A SWPPP will be prepared and ready for review by (enter date):		
A tentative schedule has been included in the SWPPP for activities such as grading, street construction, home construc	ction, etc.	
B. MONITORING PROGRAM		
A monitoring and maintenance schedule has been developed that includes inspection of the construction BMPs before anticipated storm events and after actual storm events and is available for review.		
If checked above: A qualified person has been assigned responsibility for pre-storm and post-storm BMP inspections to identify effectiveness and necessary repairs or design changes	YES N	NO
Name: Phone: _()		
C. PERMIT COMPLIANCE RESPONSIBILITY		
A qualified person has been assigned responsibility to ensure full compliance with the Permit, and to implement all elements of the Storm Water Prevention Plan including:	er Pollution	
Preparing an annual compliance evaluation	ES NO	
Name: Phone: ( )		
2. Eliminating all unauthorized discharges	ES NO	
IX. VICINITY MAP AND FEE (must show site location in relation to nearest named streets, intersections, etc.)		
	ES NO	
Have you included payment of the annual fee with this submittal?YI	ES NO	
×		
**CERTIFICATIONS  "I certify under penalty of law that this document and all attachments were prepared under my direction and supervalse a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Base person or persons who manage the system, or those persons directly responsible for gathering the information, the to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penaltic information, including the possibility of fine or imprisonment. In addition, I certify that the provisions of the permit, in and implementation of a Storm Water Pollution Prevention Plan and a Monitoring Program Plan will be complied with Printed Name:	ed on my inquiry of e information submi es for submitting fal ncluding the develo	f the itted is, Ise
Signature: Date:		_
orginature.		

Title:

# ATTACHMENT 3

# **303d Listed Water Bodies for Sedimentation**

REGION	WATER BODY NAME	CODE	POLLUTANT
1	MATTOLE RIVER	1100	Sedimentation/Siltation
1	TRINITY RIVER, SOUTH FORK	1100	Sedimentation/Siltation
1	REDWOOD CREEK	1100	Sedimentation/Siltation
1	MAD RIVER	1100	Sedimentation/Siltation
1	ELK RIVER	1100	Sedimentation/Siltation
1	EEL RIVER, SOUTH FORK	1100	Sedimentation/Siltation
1	EEL RIVER, NORTH FORK	1100	Sedimentation/Siltation
1	TRINITY RIVER	1100	Sedimentation/Siltation
1	EEL RIVER, MIDDLE FORK	1100	Sedimentation/Siltation
1	MAD RIVER	2500	Turbidity
1	TEN MILE RIVER	1100	Sedimentation/Siltation
1	NOYO RIVER	1100	Sedimentation/Siltation
1	BIG RIVER	1100	Sedimentation/Siltation
1	ALBION RIVER	1100	Sedimentation/Siltation
1	NAVARRO RIVER	1100	Sedimentation/Siltation
1	GARCIA RIVER	1100	Sedimentation/Siltation
1	GUALALA RIVER	1100	Sedimentation/Siltation
1	RUSSIAN RIVER	1100	Sedimentation/Siltation
1	TOMKI CREEK	1100	Sedimentation/Siltation
1	VAN DUZEN RIVER	1100	Sedimentation/Siltation
1	EEL RIVER DELTA	1100	Sedimentation/Siltation
1	EEL RIVER, MIDDLE MAIN FORK	1100	Sedimentation/Siltation
1	ESTERO AMERICANO	1100	Sedimentation/Siltation
1	NAVARRO RIVER DELTA	1100	Sedimentation/Siltation
1	EEL RIVER, UPPER MAIN FORK	1100	Sedimentation/Siltation
1	FRESHWATER CREEK	1100	Sedimentation/Siltation
1	SCOTT RIVER	1100	Sedimentation/Siltation
2	TOMALES BAY	1100	Sedimentation/Siltation
2	NAPA RIVER	1100	Sedimentation/Siltation
2	SONOMA CREEK	1100	Sedimentation/Siltation
2	PETALUMA RIVER	1100	Sedimentation/Siltation
2	LAGUNITAS CREEK	1100	Sedimentation/Siltation
2	WALKER CREEK	1100	Sedimentation/Siltation
2	SAN GREGORIO CREEK	1100	Sedimentation/Siltation

_			
2	SAN FRANCISQUITO CREEK	1100	Sedimentation/Siltation
2	PESCADERO CREEK (REG 2)	1100	Sedimentation/Siltation
2	BUTANO CREEK	1100	Sedimentation/Siltation
3	MORRO BAY	1100	Sedimentation/Siltation
3	SAN LORENZO RIVER ESTUARY	1100	Sedimentation/Siltation
3	SHINGLE MILL CREEK	1100	Sedimentation/Siltation
3	MOSS LANDING HARBOR	1100	Sedimentation/Siltation
3	WATSONVILLE SLOUGH	1100	Sedimentation/Siltation
3	SAN LORENZO RIVER	1100	Sedimentation/Siltation
3	ELKHORN SLOUGH	1100	Sedimentation/Siltation
3	SALINAS RIVER LAGOON (NORTH)	1100	Sedimentation/Siltation
3	GOLETA SLOUGH/ESTUARY	1100	Sedimentation/Siltation
3	CARPINTERIA MARSH (EL ESTERO	1100	Sedimentation/Siltation
3	MARSH) LOMPICO CREEK	1100	Sedimentation/Siltation
3	MORO COJO SLOUGH	1100	Sedimentation/Siltation
3	VALENCIA CREEK	1100	Sedimentation/Siltation
3	PAJARO RIVER	1100	Sedimentation/Siltation
3	RIDER GULCH CREEK	1100	Sedimentation/Siltation
3	LLAGAS CREEK	1100	Sedimentation/Siltation
3	SAN BENITO RIVER	1100	Sedimentation/Siltation
3	SALINAS RIVER	1100	Sedimentation/Siltation
3	CHORRO CREEK	1100	Sedimentation/Siltation
3	LOS OSOS CREEK	1100	Sedimentation/Siltation
3	SANTA YNEZ RIVER	1100	Sedimentation/Siltation
3	SAN ANTONIO CREEK (SANTA	1100	Sedimentation/Siltation
3	BARBARA COUNTY)	1100	Sedimentation/Siliation
3	CARBONERA CREEK	1100	Sedimentation/Siltation
3	SOQUEL LAGOON	1100	Sedimentation/Siltation
3	APTOS CREEK	1100	Sedimentation/Siltation
4	MUGU LAGOON	1100	Sedimentation/Siltation
5	HUMBUG CREEK	1100	Sedimentation/Siltation
5	PANOCHE CREEK	1100	Sedimentation/Siltation
5	FALL RIVER (PIT)	1100	Sedimentation/Siltation
6	BEAR CREEK (R6)	1100	Sedimentation/Siltation
6	MILL CREEK (3)	1100	Sedimentation/Siltation
6	HORSESHOE LAKE (2)	1100	Sedimentation/Siltation
6	BRIDGEPORT RES	1100	Sedimentation/Siltation
6	TOPAZ LAKE	1100	Sedimentation/Siltation
6	LAKE TAHOE	1100	Sedimentation/Siltation
		-	

6	PINE CREEK (2)	1100	Sedimentation/Siltation
6	TRUCKEE RIVER	1100	Sedimentation/Siltation
6	CLEARWATER CREEK	1100	Sedimentation/Siltation
6	GRAY CREEK (R6)	1100	Sedimentation/Siltation
6	WARD CREEK	1100	Sedimentation/Siltation
6	BLACKWOOD CREEK	1100	Sedimentation/Siltation
6	GOODALE CREEK	1100	Sedimentation/Siltation
6	EAST WALKER RIVER	1100	Sedimentation/Siltation
6	HEAVENLY VALLEY CREEK	1100	Sedimentation/Siltation
6	WOLF CREEK (1)	1100	Sedimentation/Siltation
6	WEST WALKER RIVER	1100	Sedimentation/Siltation
6	HOT SPRINGS CANYON CREEK	1100	Sedimentation/Siltation
6	BRONCO CREEK	1100	Sedimentation/Siltation
6	SQUAW CREEK	1100	Sedimentation/Siltation
7	IMPERIAL VALLEY DRAINS	1100	Sedimentation/Siltation
7	NEW RIVER (R7)	1100	Sedimentation/Siltation
7	ALAMO RIVER	1100	Sedimentation/Siltation
8	SAN DIEGO CREEK, REACH 1	1100	Sedimentation/Siltation
8	RATHBONE (RATHBUN) CREEK	1100	Sedimentation/Siltation
8	SAN DIEGO CREEK, REACH 2	1100	Sedimentation/Siltation
8	UPPER NEWPORT BAY ECOLOGICAL RESERVE	1100	Sedimentation/Siltation
8	BIG BEAR LAKE	1100	Sedimentation/Siltation
8	ELSINORE, LAKE	1100	Sedimentation/Siltation
9	SAN ELIJO LAGOON	1100	Sedimentation/Siltation
9	LOS PENASQUITOS LAGOON	1100	Sedimentation/Siltation
9	AGUA HEDIONDA LAGOON	1100	Sedimentation/Siltation
9	BUENA VISTA LAGOON	1100	Sedimentation/Siltation

## NEW OWNER INFORMATION AND CHANGE OF INFORMATION (COI) FORM FOR THE GENERAL CONSTRUCTION PERMIT NO. CAS000002

Owners Name:	Date:	
WDID No.:	Date of Last NOI Change:	
Prepared By:	Signature of Preparer:	

	Area Transferred (acres) <sup>1</sup>	Area Remaining (acres) <sup>2</sup>	Lot/Tract Numbers Transferred	Contact Person and Company Name of NewOwner(s)	Address(es) of the New Owner(s)	Phone # of New Owner	Is Const/Post Construction Complete? Yes/No	Date of Ownership Transfer
	column 1	column 2						
1								
2								
3								
4								
5								
6								
7								
8								
9								
10								

<sup>&</sup>lt;sup>1</sup>Use approximate area (in acres) if no exact figure is available.

Enter in column 2, line 1, the area from NOI minus the area in column 1.

Enter in column 2, line 2, the area in column 2, line 1, minus the area in line 2, column 1.

Enter in column 2, line 3, the area in column 2, line 2, minus the area in line 3, column 1, and so forth.

<sup>&</sup>lt;sup>2</sup>Calculate running total in this column as follows: